

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
LICENSED LANDSCAPE ARCHITECT					
PLANS APPROVAL DATE					
<small>THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.</small>					

PLANT QUANTITIES

BOTANICAL NAME	COMMON NAME	PLANT GROUP								PLANT BASIN					ROOT PROTECTOR	FOLIAGE PROTECTOR
		A	B	F	H	K	M	U	PACKET FERTILIZER	SOIL AMENDMENT	SLOW-RELEASE FERTILIZER	WOOD MULCH				
		EA	EA	EA		EA	EA	EA	EA	CY	LB	CY	EA	EA		
ACACIA REDOLENS 'LOW BOY'	PROSTRATE ACACIA	8,210							8,210			492.60				
BACCHARIS PILULARIS 'PIGEON POINT'	DWARF COYOTE BRUSH	3,350							3,350			201.00				
MALEPHORA LUTEA	ROCKY POINT ICE PLANT	3,840							3,840			230.40				
PARTHENOCISSUS TRICUSPIDATA	BOSTON IVY	1,542							1,542			92.52				
PHORMIUM TENAX	NEW ZEALAND FLAX	60								0.60						
RHAPHIOLEPIS INDICA	INDIAN HAWTHORNE	135								1.35						
ALOE STRIATA	CORAL ALOE		405						1,215			24.30				
CRASSULA ARGENTEA	JADE PLANT		224						672			44.80				
HETEROMELES ARBUTIFOLIA	TOYON		197						591			39.40				
SEDUM DENDROIDEUM	BUSH SEDUM			30,340							20					
SENECIO MANDRALISCAE	BLUE CHALK STICKS			125,790							80					
CARPOBROTUS EDULIS	ICE PLANT				17,440						120					
CASSIA LEPTOPHYLLA	GOLD MEDALLION TREE					2			24			0.60				
TIPUANA TIPU	TIPU TREE					4			48			1.20				
ANEMOPSIS CALIFORNICA	YERBA MANSA						666									
IVA HAYESIANA	SAN DIEGO MARSH ELDER						666									
JUNCUS ACUTUS SSP. 'LEOPOLDII'	SPINY RUSH						666									
QUERCUS LOBATA	VALLEY OAK						12		12				12	12		
CUPRESSUS SEMPERVIRENS	ITALIAN CYPRESS							36	180			7.20				
EUCALYPTUS CLADOCALYX	SUGAR GUM							10	50			2.00				
EUCALYPTUS FICIFOLIA	RED FLOWERING GUM							35	175			7.00				
TIPUANA TIPU	TIPU TREE							92	460			18.40				
PLANT BASIN SUBTOTAL										1.98	220	1161.42				
TOTAL		17,137	826	156,130	17,440	6	2,010	173	20,369				12	12		

PLANTING AREA QUANTITIES

SHEET NUMBER	WEED GERMINATION	CULTIVATION AREA		
		SOIL AMENDMENT	SLOW-RELEASE FERTILIZER	WOOD MULCH
		SQYD	CY	LB
PP-1	6,193			188
PP-2	15,971			4
PP-3	15,928			
PP-4	2,556	6	75	83
PP-5	5,479	4	50	78
PP-6	2,011			26
PP-7	3,494			140
PP-8	2,838			
PP-9		6	80	292
PP-10				177
PP-11	1,353			
PLANTING AREA SUBTOTAL	55,823	16	205	988
PLANT BASIN SUBTOTAL		1.98	220	1161.42
TOTAL	55,823	18	425	2149.4

Notice that converting cubic feet and ounces from the Plant Legend to cubic yards and pounds on the Plant Quantities Tables can result in amounts with 2 decimal places in the body of the tables. Total sums must be rounded to no more than 1 decimal place and match the Bid Item quantity in the Engineer's Estimate.

See "Generic Landscape Plan sheet, Basic Required Information" for notes regarding commas and decimals in quantity tables.

LANDSCAPE, IRRIGATION AND PLANTING EXAMPLE D2, PLANTING QUANTITIES SAMPLE

PLANTING QUANTITIES PQ-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
 Et-Plans
 PLANS PREPARATION MANUAL

REVISOR: []
 DATE: []
 CHECKED BY: []
 DESIGNED BY: []
 ARCHITECT: []
 SENIOR ARCHITECT: []
 TRANSPORTATION: []

PLANT QUANTITIES

PLANTING AREA QUANTITIES

PLANTING QUANTITIES PQ-1

EXAMPLE D2 PLANTING QUANTITIES SAMPLE - RELEASED 04/16/2020