


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	Pla	65	R11.9/R24.1		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_

PLANS APPROVAL DATE \_\_\_\_\_

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



**RUMBLE STRIP (GROUND-IN)**

SHEET No.	STATION	SIDE	SHOULDER LENGTH	CENTERLINE LENGTH
			LF	LF
L-20 TO L-24	"D13" 847+89 TO "D13" 881+71	L+	3,382	
	"D13" 847+89 TO "D13" 881+71	R+	3,382	
L-25 TO L-29	"D13" 886+33 TO "D13" 932+96	L+	4,663	
	"D13" 886+33 TO "D13" 932+96	R+	4,663	
L-29 TO L-35	"NB10" 935+04 TO "NB10" 1003+80	L+	6,876	
	"NB10" 935+04 TO "NB10" 1003+80	R+	6,876	
L-39 TO L-40	"NB10" 1045+17 TO "NB10" 1049+18	L+	401	
	"NB10" 1045+17 TO "NB10" 1049+18	R+	401	
L-40 TO L-47	"D13" 1054+77 TO "D13" 1117+45	L+	6,268	
	"D13" 1054+77 TO "D13" 1117+45	R+	6,268	
L-48 TO L-51	"D13" 1119+74 TO "D13" 1161+50	L+	4,176	
	"D13" 1119+74 TO "D13" 1161+50	R+	4,176	
L-51 TO L-52	"D13" 1164+63 TO "D13" 1173+89	L+	926	
	"D13" 1164+63 TO "D13" 1173+89	R+	926	
L-53 TO L-55	"D13" 1177+11 TO "D13" 1200+90	L+	2,379	
	"D13" 1177+11 TO "D13" 1200+90	R+	2,379	
L-59 TO L-62	"NB11"/"D13"/"D16" 1242+54 TO "D16" 1270+06	L+	2,752	
	"NB11"/"D13"/"D16" 1242+54 TO "D16" 1270+06	R+	2,752	
	CENTERLINE RUMBLE STRIP FROM PAVEMENT DELINEATION SHEETS			68,425
TOTAL			63,646	68,425

**TEMPORARY WATER POLLUTION CONTROL QUANTITIES**

SHEET No.	STATION	TEMPORARY COVER	TEMPORARY SILT FENCE	TEMPORARY STRAW BALE BARRIER	TEMPORARY DRAINAGE INLET PROTECTION	TEMPORARY CHECK DAMS (FIBER ROLL)	TEMPORARY FIBER ROLLS	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	TEMPORARY CONSTRUCTION ENTRANCE	TEMPORARY CONCRETE WASHOUTS
		SQYD	LF	LF	EA	LF	LF	SQYD	EA	EA
L-1 TO L-13	"D13" 645+66 TO "D13" 764+31	57,109	1,476	1,476	21	2,461	93,504	16,325	14	18
L-13 TO L-24	"D13" 769+71 TO "D13" 882+96	38,092	853	853		2,247	22,310	10,884	7	5
L-25 TO L-35	"D13" 885+35 TO "D13" 1000+65	49,335	2,854	2,854		2,133	38,058	14,113	7	7
L-35 TO L-47	"D13" 1000+65 TO "D13" 1117+97	40,185	984	984		2,231	34,613	11,482	7	5
L-47 TO L-64	"D13" 1118+84 TO "D13" 1296+58	85,812	8,760	8,760		4,134	30,676	24,578	14	11
TOTAL		270,533	14,927	14,927	21	13,206	219,161	77,382	49	46

**ROCK BLANKET**

SHEET No.	LOCATION	SQYD
L-66	"PARK & RIDE NORTH ENTRANCE ISLAND"	12
L-7	"ISLAND D"	103
L-8	"ISLAND E"	20
L-7	"ISLAND F"	137
L-4	"INDUSTRIAL ISLANDS" SOUTH	225
L-4	"INDUSTRIAL ISLANDS" NORTH	360
TOTAL		857

**ADJUST MANHOLE TO GRADE**

SHEET No.	LOCATION	EA
D-70	14' R+ "FR" 67+47.60	1
D-7	13' L+ "FR" 72+47.56	1
D-8	13' L+ "FR" 76+97.52	1
TOTAL		3

**TEMPORARY FENCE (TYPE ESA)**

SHEET No.	LF
L-1	568
L-3	579
L-17	371
L-18	330
L-19	566
L-20	699
L-21	179
L-24	510
L-25	298
L-33	723
L-34	237
TOTAL	5060

**SUMMARY OF QUANTITY SHEET, EXAMPLE "65 Q-13"**

**SUMMARY OF QUANTITIES**

**Q-13**

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
Caltrans

THIS EXAMPLE IS ONE OF MANY EXAMPLES OF THE VARIOUS TYPES OF PROJECT PLAN SHEETS FROM THE SAME CONSTRUCTION PROJECT, "ROUTE 65 BYPASS PROJECT."

SUMMARY OF QUANTITIES SHEET, EXAMPLE "65 Q-13" RELEASED 1/6/2012

DATE PLOTTED => 29-DEC-20  
TIME PLOTTED => 11:26