SUPERSEDES EXAMPLE RELEASED 6/29/21

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER No. Exp. CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REMOVE THERMOPLASTIC TRAFFIC STRIPES AND PAVEMENT MARKERS

SHEET No.	STATION LIMITS	STAGE	LOCATION	DETAIL No. OR PAVEMENT MARKING	REMOVE THERMOPLASTIC TRAFFIC STRIPE			REMOVE PAVEMENT MARKER	REMOVE THERMOPLASTIC PAVEMENT MARKING
					6" YELLOW (HAZARDOUS WASTE)	6" WHITE	8" WHITE		
					LF			EA	SQFT
TH-1	"B" 94+50 TO 101+43	1	LEFT	27B		693			
	"B" 102+20 TO 108+00	1	LEFT	27B		580			
	"B" 94+50 TO 108+00	1	RIGHT	27B		1350			
	"B" 96+45 TO 101+43	1	CENTER	22	996			42	
	"B" 102+20 TO 108+00	1	CENTER	22	1160			50	
	"B" 96+45 TO 101+43	1	RIGHT	38			667	21	
	"B" 102+20 TO 103+52	1	RIGHT	38			177	7	
	"B" 94+50 TO 96+45	1	CENTER	29	780			18	
	"B" 101+43 TO 102+20	1	LEFT	27C		18			
	"B" 96+50 TO 101+43	1	RIGHT	TYPE III ARROW (L)					126
	"B" 102+50 TO 102+75	1	RIGHT	TYPE VI ARROW (R)					42
TH-2	"B" 108+00 TO 119+40	1	LEFT	27B		1140			
	"B" 108+00 TO 119+40	1	RIGHT	27B		1140			
	"B" 108+00 TO 119+40	1	CENTER	22	2280			94	
TH-3	"B" 93+50 TO 94+50	2	CENTER	29	400			10	
	"B" 93+50 TO 94+50	2	RIGHT	27B		100			
	"B" 93+50 TO 94+50	2	LEFT	27B		100			
SUBTOTAL						5121	844		
TOTAL					5616	5965		242	168

When additional quantities of temporary items for traffic handling are shown on plan sheets other than the traffic handling plans, add a cross reference note regarding additional quantities on other plan sheets.

TRAFFIC HANDLING QUANTITIES SHEET, EXAMPLE 3 of 3

TRAFFIC HANDLING QUANTITIES

THQ-3

TRAFFIC HANDLING SHEET RELEASED 11/05/2021

REVISED BY | DATE REVISED

CALCULATED-DESIGNED BY | CHECKED BY

FUNCTIONAL SUPERVISOR

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION

Caltrans

LAST REVISION 00-00-00 | DATE PLOTTED => 28-OCT-2021 | TIME PLOTTED => 15:06