



BRIDGE CONSTRUCTION MEMO 145-4.0
SECTION 145-MISCELLANEOUS
INFORMATION

December 1, 1996

Page 1 of 1

Contractor Designed Temporary Bridges or other Temporary Facilities

If the Contractor proposes to construct a temporary bridge or other temporary facility across a traveled way being used by public traffic, the Contractor shall furnish the Structure Representative with working drawings and calculations detailing the location and design of the structure.

The Structure Representative will forward the aforementioned working drawings to the Sacramento Structure Construction Office for review by the Office of Structure Construction Falsework Section. The drawings should be forwarded with a letter describing loads to be supported, date Contractor wishes to begin construction, the design criteria used, and any other information pertinent to the review.

Temporary bridges or other temporary facilities not shown on the contract plans shall conform to Section 5-1.02, *Plans and Working Drawings* and Section 7-1.09, *Public Safety*, of the Standard Specifications.

Construction of the temporary bridge or other temporary facility should not be started until after the working drawings have been approved by the Engineer.